

- STANDARD NOTES:

1. CLASS OF CONCRETE 3,000PSI  
MINIMUM @ 28 DAYS.

2. REINFORCEMENT: DEFORMED GRADE  
40.

3. ALL PIPING WORKS SHALL BE  
CARRIED-OUT IN ACCORDANCE WITH  
AMERICAN WATER WORKS  
ASSOCIATION MANUALS ON WATER  
SUPPLY PRACTICES.
- NOTES:


1. BACKFILL MATERIAL WILL BE  
LEVEL VARIES FROM 1FT TO  
3FT.

2. GRADUAL COMPACTION USING  
PLATE COMPACTION UP TO  
REQUIRED LEVEL.

3. THE SIDES OF THE BACKFILLED  
AREAS WILL BE SLOPE.

4. SILT FENCE WILL BE INSTALLED  
ALONG THE SIDES OF BACKFILL  
AREAS.

5. TURF TO BE PLANTED  
COVERING ALL THE BACKFILL  
AREAS TO MITIGATE RUNOFFS.



TYPICAL DRY SYSTEM CROSS  
SECTION FOR FOUNDATION  
BELOW GROUND LEVEL 1 : 20